

cidents in such manner as the engineer may direct, at his own expense.

None of the work shall be considered as accepted which may be found defective in any part before the final acceptance of the said work by the Board of Commissioners and engineer.

Before the final acceptance of the work, the contractor shall remove any unused material or temporary work used by him and leave the work in a neat and orderly condition.

All materials furnished shall be of the best to be obtained and shall be subject to the inspection of the engineer, and if rejected shall be at once removed from the work.

#### MANAGEMENT.

The engineer shall have general charge of the work and shall set all stakes necessary for the grade and for structures and shall inspect all materials.

The superintendent to be appointed by the Board of Commissioners shall have direct charge and shall report to the engineer.

#### PAYMENTS.

Payments will be made to the contractor in monthly estimates of eighty per cent. of the work completed.

The twenty per cent. retained from each estimate will not become payable to the contractor until the final acceptance of the work by the Board of Commissioners of Vermillion County.

#### ESTIMATES OF QUANTITIES.

Gravel	6110	Cubic yards
Excavation	5777	Cubic yards
Embankment	22238	Cubic yards
Culverts	concrete 507	Cubic yds.
Masonry	1500 ft lin Barred	
Grading	1 64 - 0" plate	Gravel
	12.00 lin ft	12 feet tile
	130 . . . .	Vit Tile Culverts
	1 retaining wall	30 x 8 x
	1 . . . .	. . 100 x 18 x
	2 . 2 x 4 x 26	Concrete Culverts