cidents in such manner as the engineer may direct, at his own expense.

None of the work shall be considered as accepted which may be found defective in any part before the final acceptance of the said work by the Board of Commissioners and engineer.

Before the final acceptance of the work, the contractor shall remove any unused material or temporary work used by him and leave the work in a neat and orderly condition.

All materials furnished shall be of the best to be obtained and shall be subject to the inspection of the engineer, and if rejected shall be at once removed from the work.

MANAGEMENT.

The engineer shall have general charge of the work and shall set all stakes necessary for the grade and for structures and shall inspect all materials.

The superintendent to be appointed by the Board of Commissioners shall have direct charge and shall report to the engineer.

PAYMENTS.

Payments will be made to the contractor in monthly estimates of eighty per cent. of the work completed.

The twenty per cent. retained from each estimate will not become payable to the contractor until the final acceptance of the work by the Board of Commissioners of Vermillion County.

ESTIMATES OF QUANTITIES.

Gravel	6750 Cubic yards
Excavation 11340 Cubic yards	
Embankment 10746 Cubic yards	
ZGulverts	12" vitrified tile v28" long
zMasonry.	900 lineal feet 12"field tile.
zGradingx.	4' x 8' concrete flat top.
2 15" vitrified tile 40 long.	
2'x 10 concrete flat top.	
Add 12 ft to 4'x 6' concrete flat top.	
100 lineal feet 12" field tile .	
5'x 16' flat top, concrete.	
2-4'x4' concrete flat teps .	
12" vitrified tile 24' long · 2 12" field tile 16ft long	
24 " vitrified tile 22"long .	
1400 lineal feet 10" field tile	
Total Cubic yards of concrete 190.	